


Tree management recommendations at the time of the survey - regardless of a development (where present, ivy should be cut round the stem at the base of the tree; KJF consultancy Ltd must be informed of any defects while implementing any recommendations that are not visible from the ground);

The Common & botanical names:		Life stage:	Height (cm):	(N,E,S,W):	Canopy spread (mm):	RPA(m ²):	RPA(m):	Site (m):	R ² (%)	Physiological/structural condition, form & quality - at the time of the survey:	K/F cons:	
T1	June (Tille sp.)	Male	22	34	see plan	see plan	see plan	see plan	NA	80	A tree of high quality growing on adjacent land, the stem of the tree divides at approx. 2.2m into 3 main branches. The tree is a significant landscape tree.	Notice re...



DRAWN BY: K. J. Forkawiecz	CHECKED BY: JF	DRAWING No: TPP.R/O.03.HR.8	REV:
----------------------------	----------------	-----------------------------	------

No-dig and 3D Cellular Confinement System (if placed)
80mm Ø perforated tubing laid within RPAs (if placed)

KEEP OUT
(AVOID ANY OVERHANGING BRANCHES)

CONSTRUCTION EXCLUSION ZONE

NO LIQUIDS / MATERIALS / PLANT TO BE STORED
WITHIN THE FENCED OFF AREA

THE PROTECTIVE FENCING MUST REMAIN
IN PLACE AT ALL TIMES

(KJF CONSULTANCY LTD 07763-121432)